BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK: Improvements to roads & drains at Anjaneya Temple Area Abbigere, in Ward No.12, in Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	3	4	2	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification and directions of Engineer- In- Charge of work	cum	696.72	175.96	Rupees One Hundred Seventy Five and Paise Ninety Six Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Complete as per specfications and directions of Engineer- In- Charge of work	cum	101.85	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Paise Two Only

EXECUTIVE ENGINEER
Bruhat Ban... Mahanagara Pa...
Dasarahalli Division, Bangalor...

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Enginner
Dasarahalli Division

3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed - 2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, Complete as per specfications and directions of Engineer- In- Charge of work	cum	235.73	6491.88	Rupees Six Thousand Four Hundred Ninety One and Paise Eighty Eight Only
4	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour Complete as per specfications and directions of Engineer- In- Charge of work	Sqm	1425.75	310.58	Rupees Three
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specfications and directions of Engineer- In-Charge of work	Tonnes	16.62	59413.00	Rupees Fifty Nine Thosand Four Hundred and Thirteen Only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications and directions of Engineer- In-Charge of work	sqm	584.40	1600.00	Rupees One Thousand Six Hundred Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Enginner
Dasarahalli Division